



CITY OF ALBANY  
Public Works Department

ADDENDUM #2

**SS-25-01, Cox Creek Interceptor Sewer Phase 3**

DATE: MARCH 29, 2024

In order to clarify the intent of the Specifications and Drawings, the following provisions are provided and shall be considered part of the contract documents.

**I-20. TEMPORARY ASPHALT TRENCH PATCHING**

Add the following text:

Temporary asphalt trench patching must be completed on a weekly basis or as directed by the Engineer.

**Item No. 17 – 6-Inch PVC Sewer Service**

Add the following text:

Connections to 24-inch PVC sewer mains must be made using a 24-inch x 6-inch PVC tee.

**Item No. 18 – 4-Inch PVC Sewer Service**

Delete the entire first paragraph and replace with the following text:

Connections to 24-inch PVC sewer mains must be made using a 24-inch x 4-inch PVC tee.

**APPENDIX A**

Replace the existing Appendix A with the new attached Appendix A. The new appendix provides the ODOT permit for all work in the Interstate 5 an Airport Road right-of-way.

In order to ensure that all bidders are aware of these provisions, each bidder must sign this addendum below and attach it to the proposal.

**IMPORTANT: Failure to include a signed Addendum could result in the disqualification of your bid.**

\_\_\_\_\_  
Contractor's Signature

\_\_\_\_\_  
Date

\_\_\_\_\_  
Company Name *(please type or print)*