



**NOTES**

1. THE STORM WATER COLLECTION SYSTEM, INCLUDING CURB INLETS, SHALL BE CONSTRUCTED WITH PARTIAL STREET IMPROVEMENTS..
2. UTILITIES TO BE LOCATED AS SHOWN IN DETAIL DWG. NO. 201.
3. AGGREGATE BASE MATERIAL SHALL EXTEND TO ONE FOOT BEYOND THE FACE OF CURB, MINIMUM.
4. PLANTER STRIPS SHALL, AT A MINIMUM, BE COMPOSED OF SILTY CLAY LOAMS NATIVE TO THE AREA. IN LOCATIONS THAT ARE COMPOSED OF GRANULAR, AGGREGATE, OR OTHER IMPORTED MATERIALS, THE CONTRACTOR SHALL REMOVE AND REPLACE THE PLANTER STRIP NO LESS THAN 4' DEEP BY 4' WIDE USING NATIVE SOILS MORE CONDUCTIVE TO TREE SURVIVABILITY THROUGH THE LENGTH OF THE PLANTER STRIP.

**CITY OF ALBANY, OREGON  
PUBLIC WORKS DEPARTMENT**

**TYPICAL PARTIAL  
STREET SECTION**

NO SCALE

OCTOBER 2013

NO. 302